



Plant Hazard Analysis & Risk Assessment

Monitor
ABN: 76 159 267 679
143 Gunnedah Rd
Tamworth NSW 2340
Ph: 02 6755 6000
E: service@monitor.net.au

Model: GSR Truck Mounted Telescopic Boom Type MEWP – Models: E140P, E148T, E190THD, E209PX, E250PXJ, E290PX

Date: 10/03/2025



Person conducting assessment: T. Joyce

This Hazard Identification and Risk Assessment document is Model specific. It is based on the knowledge that all new machines of this model were/are produced to the same specification and design. It assumes all examples of this exact model currently in service to be as per the original specification, and to have been and continue to be operated and maintained in accordance with the Manufacturers requirements, and with all applicable statutory and regulatory requirements of an original example of the Model for which it was prepared. This Assessment must be reviewed by all stakeholders as required:

- Having regard to the manufacturers approved options
- Having regard to the general arrangement of miscellaneous equipment or facilities that may be provided on the plant according to the end users requirements or specification
- According to the particular circumstances under which the plant is used and maintained
- As new Hazards are identified and/or as risks are reassessed
- As existing risk control measures are revised or new risk control measures are introduced and implemented
- As and when work procedures are altered or revised
- Having regard to any unauthorised alterations or modifications made to the design or operation of the equipment

Monitor has made every attempt to identify all reasonably foreseeable operating circumstances in preparing this Assessment, however no guarantee as to the completeness of this Assessment is provided or implied.

It is the responsibility of Owners, Employers and Operators to identify all hazards associated with the use of this equipment specifically applicable to the task to be carried out and to where the equipment is to be used or located. They must assess the risk potential for each of the identified hazards and ensure that all reasonably practicable steps are taken to ensure those risks are effectively controlled.

- All operators must be trained and competent in the safe use of this particular piece of equipment, and hold appropriate qualifications as required by applicable regulatory requirements
- Operators of the equipment to which this Plant Risk Assessment refers must read and understand the Instructions for Use and Warnings contained within the Operators Manual prior to use
- All Daily Pre-Start Checks, Routine and Periodic Inspections, Maintenance and Repairs to this equipment must be carried out in accordance with the requirements of AS2550.10-2006

ID	Description of Hazard Potential		Activity	Risk control measures already implemented	Risk	Supplementary risk control measures	Risk score
	Origin	Consequence					
1	Operator Competency						
1.1	<p>Untrained operator, not following proper operating procedures.</p> <p>Distracted operator.</p> <p>Following a poor system of work.</p> <p>Operator working alone.</p>	<p>Crushing</p> <p>Impact</p> <p>Trauma</p>	<p>Set up</p> <p>Operation</p> <p>Maintenance</p>	<p>Operation instructions explained in operator's manual</p>	<p>C4</p> <p>Extreme</p>	<p>Train operators on safe use of the plant.</p> <p>Operator training should include at least the following:</p> <ul style="list-style-type: none"> • pre-operation inspections • safe operation of plant • regular maintenance tasks • understanding of plant operation • capabilities and limitations • emergency procedures <p>Do not operate the plant unless proper training has been received.</p> <p>Ensure operator's manual is kept with the plant for reference.</p> <p>Do not operate the plant when distracted, ill, excessively fatigued, or under the influence of drugs or alcohol.</p> <p>Implement appropriate system of work based on manufacturer's recommendations (e.g. operating instructions shown in operator's manual).</p>	<p>B1</p> <p>Low</p>
1.2	<p>Misuse</p> <p>Unauthorised use of plant</p>	<p>Crushing</p> <p>Impact</p> <p>Trauma</p>	<p>Operation</p>	<p>Operator's manual warns about not using the plant for other than its intended purpose.</p>	<p>C4</p> <p>Extreme</p>	<p>Do not use the MEWP for any other purpose than its intended use as explained in the operator's manual.</p> <p>Do not operate the plant unless proper training has been received.</p> <p>Keys are not to remain in an unattended machine.</p>	<p>B1</p> <p>Low</p>

ID	Description of Hazard Potential		Activity	Risk control measures already implemented	Risk	Supplementary risk control measures	Risk score
	Origin	Consequence					
1.3	Driving truck	Vehicle accident	Driving			Must have suitable licence i.e. MR Travel at road speeds indicated. Drive to conditions. Unit must not be moved unless the platform is lowered and the stabilisers withdrawn.	
2	Plant Limitations						
2.1	Plant overload causing - overturning - structural failure	Overturning Crushing	Driving Operation	Maximum Rated Capacity (MRC) displayed on basket.	C4 Extreme	Learn and understand plant limitations. Consider weight of all workers, tools and equipment to be loaded into basket. Do not exceed work platform capacity. Regularly inspect the MEWP as per maintenance schedule to ensure integrity of structural members. Report any faults to the supervisor immediately. Records must be kept in the maintenance/log book.	A2 Low
2.2	Excessive incline causing plant to overturn	Overturning	Driving Operation	Plant limitations given in Operator's Manual that the machine must not to be set up on slopes exceeding 5° in either direction	C3 High	Do not drive the plant over ground slopes which exceeds its limitations. Conduct site risk assessment to determine suitability of job site before starting any work. Ensure that the four stabilisers' pads are set up on firm sound solid surface and the base is level prior to commencing work.	B2 Low

ID	Description of Hazard Potential		Activity	Risk control measures already implemented	Risk	Supplementary risk control measures	Risk score
	Origin	Consequence					
2.3	Parking on a slope	Runaway vehicle Overturning	Set-up Operation	Truck fitted with parking brake.	C3 High	Prior to leaving the unit that the park brake must be applied and the wheels chocked.	A2 Low
2.4	Excessive wind force causing overturning.	Overturning	Operation	Follow maximum wind speed rating listed in the operator's manual (45Km/h).	C3 High	Constantly monitor wind speed when operating in wind sensitive areas.	B2 Low
2.5	Instability due to road wheels being in contact with supporting surface.	Overturning	Operation	Operator's manual states that road wheels must be clear of the supporting surface when the unit is set up for operations.	C4 Extreme	Visually inspect wheels clear of surface when the levelling of the unit has been completed.	B2 Low
2.6	Supporting structure beneath the stabilisers being incapable of withstanding the loads imposed by the truck mounted boom e.g a wharf.	Overturning	Operation	Operator's manual has nominated the maximum load on the stabilisers.	C4 Extreme	Prior to setting up the unit upon an unknown structure or surface the operator may need to consult an external party to ensure that it will adequately support the unit.	B2 Low
3	Plant at worksite						
3.1	Collision with - site infrastructure - other plant and/or pedestrians - other infrastructure	Crushing Impact	Operation Driving	Motion audible and visual alarm present.	C3 High	Beware of any obstructions around the work area; survey the area before moving the plant. Beware of other plant and persons around the work area, in particular when travelling around corners or blind spots. Ensure that prior to moving the unit that the stabilisers are correctly stowed. Operator to be aware of overall height of unit with boom stowed.	B2 Low

ID	Description of Hazard Potential		Activity	Risk control measures already implemented	Risk	Supplementary risk control measures	Risk score
	Origin	Consequence					
3.2	Exhaust fume build-up in poorly ventilated areas.	Asphyxiation	Operation		C4 Extreme	Ensure there is enough ventilation at the job site whenever combustion engine is used to operate the plant. May require forced mechanical ventilation.	B1 Low
3.3	Plant positioned near or driven over large depressions / obstacles.	Overturning Collapse	Operation Driving	Stabiliser pads provided with the plant. Operator's manual recommends avoiding working near ditches and trenches and using stabiliser pads on soft ground. Maximum ground pressure is displayed near stabilisers and in operator's manual.	C4 Extreme	Always maintain a safe distance from ditches, trenches or pit walls while operating plant. Plan a route to safely bring the plant to the job site. Avoid driving over large obstacles or depressions. Assess the ground conditions before setting up the plant: use dunnage under stabilisers if necessary. Deploy stabilisers close to ground to help prevent overturning.	B2 Low
4	Operation						
4.1	Driving on steep ground	Overturning Crushing	Driving Set up	Follow maximum inclination limits set by manufacturer. Found in plant manual.	A5 High	Carry out job site risk assessment to determine suitability of the site before commencing any work. Avoid driving on steep ground; find alternative routes whenever possible. Do not stand on the lower side of the plant while driving on steep ground.	A1 Low
4.2	Sudden change of direction when driving	Crushing Impact	Set up Driving		C3 High	Bystanders to stand a safe distance away from the moving plant and	A1 Low

ID	Description of Hazard Potential		Activity	Risk control measures already implemented	Risk	Supplementary risk control measures	Risk score
	Origin	Consequence					
						check no person is around it before driving.	
4.3	Travelling with the boom extended	Crushing Overturning	Driving	Monitoring device for retracted telescopic booms (if available): consists of a microswitch detecting the extension of the extensible elements making up the telescopic boom. Its operation is indicated by two red indicator lights provided in the cab control station and stabiliser control station.	A2 Low	Check indicator lights prior to leaving and monitor during travelling.	A2 Low
4.4	Overturning	Crushing Falling Death	Set up Operation Emergency Maintenance Transport	Stability calculations supplied by manufacturer demonstrate plant stability when operated within rated capacity and environmental limitations. Plant stability tested	C5 Extreme	Do not exceed plant's rated capacity and environmental limitations. Pay attention to ground conditions when driving and setting up the plant. Know and understand plant's stability limits before operating the emergency system. When using the emergency recovery system, fully close the telescopic boom before attempting any other movement.	B1 Low
4.5	Excessive chassis inclination	Crushing Falling	Operation	The model is provided with four hydraulic stabiliser systems to level the unit. The comes with indicator lights and a sight level with base frame within 1° MAX. of level.	B5 Extreme	Visually to check to ensure that all stabilisers are in firm contact with the supporting surface and that the machine base is level and that the indicator lights are illuminated.	A1 Low

ID	Description of Hazard Potential		Activity	Risk control measures already implemented	Risk	Supplementary risk control measures	Risk score
	Origin	Consequence					
4.6	Reach and moment-sensing system failure	Crushing	Operation	Operator's manual recommends pre-operation check of safety devices at the start of every shift.	C5 Extreme	Always perform pre-operation inspection. Do not operate a faulty plant.	A1 Low
4.7	Excessive work platform inclination	Falling	Operation	Work platform automatic levelling system present.	A5 High	Wear fall-arrest harness. Regularly check operation of work platform levelling system. Inhibit work platform movements which cause the work platform angle to exceed 10 degrees.	A1 Low
4.8	Operator control	Worker falls from basket Overturning Impact	Operation		C5 Extreme	Operate the drive control levers gently in order to avoid abrupt and jerky movements. When moving, pay special attention to stability and the dimensions, especially the length, of the machine. Wear safety harnesses and keep them fastened whenever operating the machine.	B2 Low
4.09	Truck mounted boom is operated while on a moving surface or vehicle.	Overturning Crushing Impact	Operation		C5 Extreme	Unit must only be operated when it is on a static, firm level surface.	B2 Low
4.10	Uncontrolled movement of plant components i.e. stabilisers	Crushing Impact Shearing	Set up Operation Maintenance Cleaning Troubleshoot	Prestart inspection as per manufacturers recommendation. Crush, shear hazard decals on machine.	C3 High	Isolate power to plant and remove the main switch key when performing maintenance and cleaning tasks. Stay clear of components which may swing or drop unexpectedly. Maintenance to be carried out by a competent person.	B2 Low

ID	Description of Hazard Potential		Activity	Risk control measures already implemented	Risk	Supplementary risk control measures	Risk score
	Origin	Consequence					
						Pay attention to crush and shear hazard decals to machine.	
4.11	Inadvertent operation of controls	Crushing Impact	Set up Operation Maintenance Emergency	Plant movement stops when controls are released. Plant controls protected with function-enable button / foot switch. Work platform controls protected with fixed barriers.	C5 Extreme	Always depress the emergency stop button whenever the plant is not being operated. Understand the risks associated with inadvertent operation and avoid placing yourself in compromising positions.	B2 Low
4.12	Lowering / Raising - stabilisers - work platform Moving parts	Crushing Impact Shearing Drawing Severing	Set up Operation Maintenance Troubleshoot	Decals indicating crush hazards affixed to plant.	C4 Extreme	Take appropriate safety measures e.g. barricades to keep people away from plant's operating areas. Ensure all persons are clear of moving components before performing a movement. Ensure basket is horizontal and if necessary, adjust it by means of the controls prior to moving from stowed position. Maintenance to be carried out by a competent person.	B2 Low
4.13	Entering/exiting the work platform (basket)	Falls	Operation	Operator is instructed not to jump from the platform and to use the stepping facilities provided.	C3 High	Do not move between the basket and a structure outside the machine, machine stability could be jeopardised. Workers and equipment must enter and exit the basket only when it is stowed. Always face inwards and maintain 3-points of contact when entering or exiting the basket.	B1 Low
4.14	Manoeuvring the work platform near fixed structures	Crushing Shearing	Set up Operation	Work platform fitted with inner handrails to prevent crushing of	C4 Extreme	Do not reach out or have body parts outside the work platform's	B1 Low

ID	Description of Hazard Potential		Activity	Risk control measures already implemented	Risk	Supplementary risk control measures	Risk score
	Origin	Consequence					
				fingers/hands by fixed structures.		rails while the work platform is moving. Beware of overhead obstructions during plant movement.	
4.15	Unexpected work platform movement.	Impact Crushing Falling	Operation	Harness anchor points fitted to work platform.	B5 Extreme	Wear safety harness when in the work platform. Hold on to grab rails during platform movement.	B1 Low
4.16	Platform overload	Crushing Falling Impact	Operation	Plant limitation displayed on work platform and Operator's Manual. Plant fitted with load and moment sensing system.	B5 Extreme	Do not overload the work platform.	B1 Low
4.17	Faulty/out of calibration load and moment indicator	Crushing Impact Overturning	Operation		B5 Extreme	Perform periodic testing and calibration of load and moment indicator as per manufacturer's recommendations and/or local authority requirements.	B1 Low
4.18	Falling objects	Falling objects Impact	Operation	Barricade work area under fall zone to create a no-go zone.	C3 High	Secure items such as tools and consumables which could fall from basket. Lay items flat and evenly across the floor of the basket.	B2 Low
4.19	Large surface area objects on the plant.	Overturning	Operation Maintenance Storage		B4 High	Do not place large surface area objects on the plant, such as panels or banners.	A1 Low
4.20	Falling from basket	Fall Death	Operation	Drop gate. Lanyard attachment point.	C5 Extreme	Check that the sliding bar which protects the opening of the basket is closed and positioned correctly. Safety harness to be worn at all times and secured to the designated hook in the basket.	B2 Low

ID	Description of Hazard Potential		Activity	Risk control measures already implemented	Risk	Supplementary risk control measures	Risk score
	Origin	Consequence					
4.21	Jib boom knuckle at head height of operator in the work platform	Impact	Operation Maintenance		B2 Low	Beware of jib boom knuckle when closing the jib boom.	A1 Low
4.22	Raising truck mounted boom	Crush between fixed structure and basket	Operation	Check surroundings prior to starting and continually throughout job.	C4 Extreme	Be aware of potential crush hazards in the direction of movement before moving the work platform. Hard hat may be required if working near overhead obstructions.	B2 Low
4.23	Removal/installation of work platform	Impact Musculoskeletal injury	Maintenance Transport		D3 High	2-person lift is required to lift the work platform in position. Use mechanical aids such as forklift or floor crane to support the basket.	A1 Low
4.24	Operation of hand pump	Fatigue Muscle strain	Emergency	Electric auxiliary pump may be used for emergency recovery.	B3 Medium	Use sound ergonomic principles to minimise the risk of injuries.	A1 Low
4.25	Faulty/out of order, or poorly maintained plant	Crushing Impact Trauma	Operation Emergency Maintenance	Operator's manual outlines plant maintenance schedule. Current maintenance inspections up to date as per manufacturers recommendation.	B4 High	Always perform pre-operation inspection before operating the plant. Implement 'tag out' procedure to isolate faulty/out of order plants. Do not use an 'out of order' plant. Record all faults in logbook. Perform plant maintenance as per manufacturer's maintenance schedule. Keep maintenance records / plant logbook up to date.	B1 Low

ID	Description of Hazard Potential		Activity	Risk control measures already implemented	Risk	Supplementary risk control measures	Risk score
	Origin	Consequence					
4.26	Plant modifications after completion of risk assessment.	Crushing Overturning	Operation Set up		C5 Extreme	Ensure modifications made to the plant are inspected, assessed, and approved by a competent person. Review hazard analysis and risk assessment after plant modifications.	B1 Low
5	Plant Failure						
5.1	Plant failure including: - malfunction of control devices - structural failure of machine components - failure of lift / tie down points	Crushing Impact	Operation	Follow routine maintenance inspections by qualified person as per manufacturers recommendation. Prestart inspection as per manufacturers recommendation. Structural calculation supplied by manufacturer demonstrate suitability of structural members for the load combinations considered.	B5 Extreme	Carry out pre-operational function tests of safety related functions at the start of every shift. Beware of risks associated with inadvertent operation of the machine, avoid compromising machine positions. Familiarise with location of emergency stop buttons. Regularly inspect the MEWP as per maintenance schedule to ensure integrity of structural members.	B2 Low
5.2	Failure of basket to lower.	Falling	Emergency	Plant fitted with emergency lowering system. Emergency retrieval procedure included in Operator's Manual and on decals on the plant near emergency controls.	C5 Extreme	Beware of the dangers of working at heights. Become familiar with emergency rescue procedures.	B1 Low
5.3	Emergency recovery controls failure	Health deterioration Death	Emergency		C4 Extreme	Regularly test emergency recovery system.	A1 Low
5.4	Burst hydraulic hose	Crushing Overturning Burn Skin irritation	Set up Operation Maintenance	Counter-balance valves fitted on lift and extension cylinders.	A3 Medium	Check hydraulic hose condition during periodic maintenance. Report and "tag out of service" if identified.	A2 Low
5.5	Excessive hydraulic oil pressure.	Impact Crushing	Set up Operation	Plant fitted with pressure relief valve.	C3 High	Check pressure settings during preventative maintenance.	A1 Low

ID	Description of Hazard Potential		Activity	Risk control measures already implemented	Risk	Supplementary risk control measures	Risk score
	Origin	Consequence					
5.6	Loss of hydraulic pressure	Crushing Injection	Operation Emergency Maintenance	Hydraulic rams fitted with failsafe lock valves. A relief valve is fitted within the system which limits the capacity of the machine. The manufacturer has provided lock valves within the hydraulic systems.	A5 High	Do not operate a faulty plant. Check operation of counterbalance valves as recommended by manufacturer. Do not disconnect hydraulic hoses, loosen off valves or fittings to attempt the recover a broken-down plant; follow emergency recovery procedures instead. Always support truck mounted booms, stabilisers, etc before disconnecting hoses or valves.	B1 Low
6	Electrical						
6.1	Electronic component failure	Crushing	Operation	Electrical and electronic components comply with design safety categories stipulated in AS 1418.10-2011. Emergency stop buttons available at each control station.	A5 High	Become familiar with location of emergency stop buttons. Perform function tests, including operation of E-Stops at the start of every shift. Ensure that the operator is instructed that in an emergency to call a person or persons nearby and require them to knock the emergency stop button at the ground station level should the machines operation fail to respond to the upper emergency stop button.	A1 Low
6.2	Contact with live conductors under plant cover	Shock Electrocution	Emergency Maintenance		C5 Extreme	Do not touch terminals/wires inside the electric cabinet. Keep electric cabinet closed and locked at all times.	A2 Low

ID	Description of Hazard Potential		Activity	Risk control measures already implemented	Risk	Supplementary risk control measures	Risk score
	Origin	Consequence					
6.3	Overhead power lines	Electrocution	Set up Operation Transport Emergency	Operator's manual and decals show minimum safe distances when working near power lines. Decal on work platform states that the plant is not electrically insulated.	C5 Extreme	Follow local authorities' regulations regarding safe distance from powerlines. Ensure overhead power is switched off or use a spotter if safe distances cannot be maintained. Be mindful of overhead power lines on roads when transporting the plant on a vehicle. Do not move, approach or come in contact with a plant that has contacted power lines until network power has been isolated.	A3 Medium
6.4	Lightning	Electrocution Shock	Set up Operation		A5 High	Do not use the plant during a thunderstorm.	A1 Low

RISK MATRIX						ACTION	HEIRACHY OF CONTROLS
		CONSEQUENCE					
		1. Insignificant	2. Minor	3. Moderate	4. Major	5. Catastrophic	
LIKELIHOOD	E. Almost Certain Is expected to occur immediately or within a short timeframe	HIGH	HIGH	EXTREME	EXTREME	EXTREME	EXTREME – Do not proceed, until further control measures are implemented to lower the risk. Senior management attention required. HIGH – Review and introduce additional controls to lower level of risk. Needs senior management attention. MEDIUM – Monitor and maintain supervision and controls. Specify management responsibility. LOW – Monitor and manage by routine procedures and monitoring.
	D. Likely Will probably occur in most circumstances	MEDIUM	HIGH	HIGH	EXTREME	EXTREME	
	C. Possible Could happen and has occurred here or elsewhere	LOW	MEDIUM	HIGH	EXTREME	EXTREME	
	B. Unlikely Unlikely to occur	LOW	LOW	MEDIUM	HIGH	EXTREME	
	A. Rare Not expected to occur	LOW	LOW	MEDIUM	HIGH	HIGH	

CONSEQUENCE DESCRIPTORS			
SEVERITY	SAFETY	ENVIRONMENT	BUSINESS
5. Catastrophic	Potential for incident resulting in serious damage and/or fatality	The aspect is legally or contract regulated and has the potential for a disastrous long term impact resulting in prosecution.	Loss > \$1M
4. Major	Potential for incident resulting in serious damage and/or permanent disabling illness or injury	The aspect is legally or contract regulated and has the potential for a serious long term impact resulting in prosecution.	Loss of service provision
3. Moderate	Potential for incident resulting in significant damage and/or temporary disabling illness or injury	Significant environmental aspect with short term impact resulting in improvement notice.	Loss \$100K - \$1M
2. Minor	Potential for incident resulting in moderate damage and/or requiring medical treatment.	The aspect is legally or contract regulated and has the potential for a moderate reversible short term impact resulting in an improvement notice.	Prolonged reduction in service provision or productivity
1. Insignificant	Potential for incident resulting in minor damage and/or injury requiring first aid treatment	The aspect is not legally or contract regulated and has the potential for a minor negligible impact.	Loss \$10K - \$100K